

Noble Voyager



Drillship

General description

The Noble Voyager is a drill ship, with dual well centers designed for reliable drilling and well abandonment operations in deepwater and ultra-deepwater depths. Its hull design with ample storage and deck space, supports efficient well construction, intervention, and decommissioning activities. The Noble Voyager has a proven track record of reducing well construction time by a relentless focus on efficiency. It is outfitted with a dual BOP system, dual mud systems and an integrated CML managed pressure system.

General specifications

Design	Samsung 96K
Year built/upgraded	2013
Year entered service	2013
Builder	SHI, Korea
Flag	Marshall Islands
Classification	ABS, Drilling Unit, A1, AMS, ACCU, DPS-3, BWT+, CRC, HELIDK(SRF), NBL, PMP,RW SH-DLA UWILD
MODU Code	2009
Overall Length	748 ft
Draft	39.4 ft (operating), 27.9 (transit)
Depth	62.3 ft
Displacement	96,500 t
Variable deck load	20,000 t
Transit speed	12 knots
Water depth	12,000 ft
Drilling depth	40,000 ft
Accommodation	230
Hook load	2.8MM lbs (main), 2.0MM lbs (aux)
Moonpool	84 ft x 41 ft

Applications

NORMS	Real Time Monitoring	Ops Performance Tool	H56	OnTheGo
			RigFlow/Rig Pulse	

These specifications are intended for general reference purposes only. Actual equipment may vary upon the contract situation and customer needs.

First Choice Offshore®



For more information please contact: noblemarketing@noblecorp.com

Storage capacity

Liquid mud	15,970 bbls
Base oil	6,277 bbls
Brine	4,887 bbls
Bulk cement	7,981 cuft
Bulk bentonite	7,981 cuft
Bulk barite	15,962 cuft
Sacks	5,000
Fuel	39,000 bbls
Drill water	15,160 bbls
Potable water	8,960 bbls

Drilling equipment

Derrick	210 ft x 60 ft x 80 ft derrick to handle 135 ft tubular. 1 x NOV 2,800 kips crown block (main), 1 x NOV 2,000 kips crown block (aux)
Drawworks	1 x NOV AHD – 1250, 6,700 kW (main) 1 x NOV AHD – 1000, 5,100 kW (aux)
Motion Compensator	AHC (main, aux)
Rotary Table	1 x Varco BJ RST 75-1/2" hydraulic (main) 1 x Varco BJ RST 60-1/2" hydraulic (aux)
Top Drive	2 x TDX-1250, 2,500 kips rotating (main, aux)
Tubular Handling	2 x NOV Hydra racker HR-IV-ER
Fingerboard capacity	375 stds 5 7/8" - 6 5/8", 90stds 5", 88 stds Casing
Mud Pumps	5 x NOV 14-P-220, 7,500 psi
Solids Control System	7 x VMS 300 shale shakers
Iron Roughneck	1 x NOV ARN 270 (main), 199,000 ftlbs m/u 1 x NOV ARN 200 (aux), 105,000 ftlbs m/u

Sub sea equipment

Diverter	GE Vetco Gray-CSO, 21 1/4" x 500 psi
Dual BOP	Yes
BOP stack	2 x HMM, 6 ram each, 18 3/4" x 15k psi, 1 x HMM Vetco Gray SHD-H4 well head connector
LMRP	2 x HMM GX 18-10, BTM FLG 18 3/4" x 10k psi, 1x HMM Vetco Gray HAR ExF H4 connector.
C&K manifold	WOM 15K
Marine riser	GE Vetco MR-6H SE, CLIP, 90 ft length, 10,000 ft
Tensioners	16 x NOV DWRT-225-50, 225kips each, 50ft stroke
XT Carts	1 x 230 t Xmas Tree Carrier,

Noble Voyager



Noble Voyager Rig Crew

Power generation

Closed Bus	Yes
Main power	6 x 7,248 kW, Doosan MAN at 720 rpm
Electrical power	6 x 7,000 kW, 11kV, generators
Emergency power	1 x 1,900 kW STX, generator 1,350 kW, 450V

Cranes

Main cranes	4 x 85 t electro-hydraulic knuckle-boom cranes at 18 m (59 ft) radius
Subsea cranes	N/A
X-Mas Tree / BOP	2 x 75 t Xmas Tree overhead crane to move Xmas trees well center w/ capacity
Other	N/A

Other Systems

MPD	CML EDR, control system EDR
Burner booms	1 x NOV 15,000 BOPD, Swan Neck Type
Dual Well Centers	Yes
Automation	Cyberbase, MMC, NOVOS, PIMS, Softspeed
Red Zone Management	NOV red zone manager, camera with equipment control (installation 2026)
On the Go	Yes
H56 Enabled	No
Data Infrastructure	Real time data monitoring
Other	N/A

Real Time Data Provision

Drilling	VMS	BOP

These specifications are intended for general reference purposes only. Actual equipment may vary upon the contract situation and customer needs.

First Choice Offshore®



For more information please contact: noblemarketing@noblecorp.com

Unique Capabilities and Enhancements

Drill floor	Identical topdrives on main and aux, TDX-1250, 2,500 kips rotating (main, aux)
Energy Efficiency	Closed bus power distribution system
MPD	CML system installed

Station keeping / Propulsion system

Mooring system	N/A
Mooring winches	N/A
Thrusters	6 x 5,500 kW, FS3510/NU Wartsila LIPS fixed pitch, in water removable thrusters
DP system	Kongsberg SDP-32 System for DPS-3 Operations
Position reference systems	4 x HPR / 3 x DGPS

